

SCHOOL DISTRICT OF OKALOOSA COUNTY
Purchasing Department

SUPERINTENDENT OF SCHOOLS
MARCUS D. CHAMBERS

ATTORNEY TO THE BOARD
C. JEFFREY McINNIS, ESQ.

PGM. DIRECTOR - PURCHASING
VINCE WINDHAM, CPPB



BOARD MEMBERS
TIM BRYANT
LINDA EVANCHYK
D. PARKER DESTIN
BRETT HINELY
LAMAR WHITE

ADDENDUM NO. 1 OF 1

To: All Bidders

From: Jessica Chandler *JC*
Buyer - Purchasing

Subject: Addendum No. 1
ITB 25-07 Crestview High Auto Lab Remodel

Date: April 3, 2025

Please see the information listed below for clarification and/or additional requirements concerning ITB 25-07. The requirements stated in this addendum supersede and supplement all requirements previously stated in the original ITB documents, and become part of the contract documents for this project.

This is Page 1 of 2 Pages

I HAVE READ AND UNDERSTAND THE ABOVE REQUIREMENTS. THIS ADDENDUM MUST BE SIGNED BY AN AUTHORIZED VENDOR REPRESENTATIVE. FAILURE TO SIGN AND RETURN THIS ADDENDUM BY THE DEADLINE FOR SUBMISSION OF PROPOSALS MAY RESULT IN YOUR PROPOSAL BEING DEEMED NON-RESPONSIVE.

COMPANY

AUTHORIZED SIGNATURE

**Okaloosa County School District
ITB 25-07**

- Q1. Sheet A-2 calls for a ½ lite 3070 hollow metal door and frame in what appears to be a storefront system. Please confirm a storefront system and hollow metal door and frame is intended for this location. Contractor believes the intent is to have the hollow metal door installed in a drywall system and the storefront was mistakenly added.
- A1. The ½ Lite 3070 hollow metal door and frame in the new storefront system is incorrectly placed. Please refer to the elevation drawing of the storefront wall system for the correct location of the door (s).
- Q2. Sheet A.2 Proposed Remodel/Life Safety Plan shows a storefront system with a roll up door and 3979 storefront door on the interior of the building but the elevation on Page 3 shows a double door storefront system with no roll up door. Keynote B on same Sheet also states storefront system is “By Others”. Please clarify if Contractor is to provide a storefront system here and what the intent of the design is to be.
- A2. The contractor is to provide a storefront system with a double door as shown on page 3.
- Q3. Sheet A.2/Keynote A instructs Contractor to “Epoxy All Floors” but no specification is provided. Would Owner like Contractor to specify a material?
- A3. The Contractor shall submit proposed materials for approval by the Owner.